


Adresa imobilului:
Judetul Arges, UAT Rucar
Intravilan
Categorie de folosinta - Curti Constructii
Punctul Acasa
CF/CAD: 83616
S = 0.0630 ha

PLAN DE SITUATIE
SC. 1:200



Inventar de coordonate
Sistem de proiectie Stereografic 1970
Plan de referinta cote "Marea Neagra 1975"

Nr. Crt.	N(m)	E(m)	Z(m)
1	432714.52	514273.52	709.229
2	432689.96	514284.07	709.085
3	432689.60	514284.23	709.099
4	432686.32	514277.87	707.835
5	432682.86	514271.63	706.533
6	432679.57	514266.32	705.564
7	432682.09	514264.94	705.949
8	432691.44	514259.88	708.081
9	432705.82	514251.52	708.329
10	432709.50	514260.30	708.693
11	432711.49	514264.89	708.903
12	432715.11	514273.29	709.112

Horatiu
Hanganu

Digitally signed by Horatiu Hanganu
DN: c=RO, o=GEOPROCESSING SRL,
cn=Horatiu Hanganu,
serialNumber=HH5,
givenName=Horatiu, sn=Hanganu,
2.5.4.97=RO21556107
Date: 2022.07.13 09:59:12 +03'00'



LEGENDA

- Limita de proprietate - gard din lemn
- Constructie proiectata
- Trotuar de garda
- Suprafata pietruita (acces + parcare)
- Zona verde
- Gard viu (spirea, buxus) h=1,20m
- Acces pe amplasament
- Accese in cladire
- B.V. Bazin vidanjabil

St= 630 mp
Sc=Sd= 167,60 mp
S_{pietruita, trotuar de garda} = 211,72 mp
S_{zona verde} = 250,68 mp

$$POT = \frac{Sc}{St} \times 100 = \frac{167,60}{630} \times 100 = 27\%$$
$$CUT = \frac{Sd}{St} = \frac{167,60}{630} = 0,27$$

Clasa de importanta IV conf. P100-1/2013
Categorie de importanta D (reduca) conf. HG 766/97

EXPERT				
VERIFICATOR				
SPECIFICATIE	NUME	SEMNATURA	CERINTA	REFERAT/EXPERTIZA/NR./DATA
S.C. Bucon Invest S.R.L., Brasov NR. J/08/386/2006 Str. AVRAM IANCU, Nr.49, Sc. A, Ap.1, TEL: 0268 312 392				BENEFICIAR: Fundatia Conservation Carpathia PR. NR. 68/2022
SPECIFICATIE	NUME	SEMNATURA	SCARA 1:200	TITLU PROIECT: Centru de vizitare zimbri si castori Life 18 NAT/RO/001082 Rucar nr.124A, jud. Arges
SEF PROIECT	arh. Buna I.			FAZA D.T.A.C.+D.T.
PROIECTAT	arh. Buna I.		DATA 2022	TITLU PLANSA: Plan de situatie
DESENAT	Kiss A.			PL. NR. A01